WATER GENERAL NOTES

GENERAL:

1. ALL MATERIALS AND CONSTRUCTION METHODS SHALL BE IN CONFORMANCE WITH THE LATEST EDITION OF THE "CITY OF BATTLE GROUND CONSTRUCTION STANDARDS" AND THE LATEST EDITION OF THE "STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND MUNICIPAL CONSTRUCTION" HEREINAFTER REFERRED TO AS THE "STANDARD SPECIFICATIONS" PREPARED BY THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION, EXCEPT AS NOTED HEREIN OR ON THE STANDARD PLANS. ALL REFERENCES TO AWWA AND/OR APWA SPECIFICATIONS SHALL MEAN THEIR LATEST REVISION.

2. ALL WATER LINE CONSTRUCTION IS SUBJECT TO INSPECTION AND APPROVAL BY THE CITY OF BATTLE GROUND, PRIOR TO COVER. ALL TESTING SHALL BE APPROVED PRIOR TO PAVING. THE CONTRACTOR SHALL NOTIFY THE ENGINEERING OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF CONSTUCTION. A PRE-CONSTRUCTION MEETING IS REQUIRED PRIOR TO THE BEGINNING OF CONSTRUCTION.

3. ALL PIPES FURNISHED SHALL BE NEW, AND CONFORM TO THE REQUIREMENTS OF AWWA DI CL52.

4. A TRAFFIC CONTROL PLAN IS REQUIRED PRIOR TO CONSTRUCTION WITHIN A CITY OR CLARK COUNTY RIGHT-OF-WAY.

5. WHERE EXISTING SERVICE MUST BE INTERRUPTED, THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE CITY AND NOTIFY ALL CUSTOMERS AFFECTED AS TO THE DATE AND DURATION OF THE INTERRUPTION. NOTIFICATION MUST BE DONE TWO (2) WORKING DAYS IN ADVANCE OF INTERRUPTION. THE CONTRACTOR SHALL SCHEDULE CONSTRUCTION TO PROVIDE MINIMUM INTERRUPTION OF SERVICES AS DETERMINED BY THE INSPECTOR. UNDER NO CIRCUMSTANCES SHALL A CONTRACTOR SCHEDULE A WATER MAIN SHUT-DOWN WITHOUT THE REQUIRED 48 HOUR NOTICE. THE CONTRACTOR SHALL NOT OPERATE THE CITY'S WATER FACILITIES WITHOUT APPROVAL FROM THE CONSTRUCTION INSPECTOR.

6. WHEN EXTENDING AN EXISTING LINE THE CONTRACTOR IS REQUIRED TO INSTALL A VALVE AT THE END OF THE LINE IF ONE DOES NOT EXIST PRIOR TO MAKING A CONNECTION TO THE NEW LINE. THE VALVE MUST REMAIN CLOSED UNTIL THE NEW LINE HAS BEEN TESTED AND ACCEPTED BY THE CITY. AS AN ALTERNATIVE THE CONTRACTOR MAY CONSTRUCT AND TEST THE NEW LINE PRIOR TO MAKING THE FINAL CONNECTION TO THE EXISTING LINE. THE LINE MUST BE ACCEPTED BY THE CITY BEFORE MAKING THE FINAL CONNECTION.

7. CONTRACTOR TO CONTACT FIRE DISTRICT 11 AT (360) 687-2171 FOR FIRE FLOW TEST PRIOR TO ENGINEERING ACCEPTANCE.

WATER METERS:

8. ALL WATER METERS WILL BE FURNISHED AND INSTALLED BY THE CITY.

WATER GENERAL NOTES

PLAN #

THE CITY OF BATTLE GROUND

CITY OF BATTLE GROUND
APPROVED

9/24/07

CITY ENGINEER DATE

REVISIONS:	DATE:	DRAWN:	DESIGNED:
1	8/12/98	BSG	GGH
2	8/30/05	ALL	MCH
3	4/16/07	JMH	MCH
4	9/21/07	MCH	MCH

WA-1.0